



Central University of Orissa

(Established by an Act of Parliament)

Ref:- XXX111-52/2013/

Date:-06.03.2013

Quotation for construction of temporary canteen at Central University of Orissa, New Campus, Sunabeda.

The permanent campus of Central University of Orissa is coming up at Sunabeda. A temporary canteen with G.I Sheet roof of Plinth area 95.55sqm/1028.63sqft is to be constructed near temporary academic block. The detailed specifications for construction of the canteen is attached.

Terms and conditions:-

1. The civil contractors and agencies possessing class c and above valid license with minimum of 3yrs of experience in such construction works with Govt. /Semi Govt. /Autonomous Bodies may submit sealed quotation by deputing their representative if required for assessing the site position at Sunabeda.
2. The contractors are required to provide copies of civil license, VAT clearance certificate, PAN number and TIN number along with the tender.
3. The contractors are requested to submit EMD of Rs.40, 000.00 by DD drawn in favour of Central University of Orissa payable at Koraput in any nationalized bank.
4. The quoted rates by the contractors shall be inclusive of all taxes.

The interested contractors may feel free to contact the undersigned for further clarifications, if any on Mob.No.9692244940 and also log on to our web site www.cuo.ac.in for more details about the work.

The Quotation shall reach the undersigned on or before 20.03.2013 by 3 P.M at the address given below. The same will be opened on 20.03.2013 at 3.30 P.M in the presence of the Representatives of the renderers.

Address:

The Registrar
Central University of Orissa, Koraput
At:-Landiguda, Po:-Koraput,
Dist:-Koraput (odisha)
Pin:-764 020

REGISTRAR

DETAILED SPECIFICATIONS/BILL OF QUOTATIONS:-

SL No.	Description	No	Unity	Qty.	Rate (Rs.)	Amount (Rs.)
1.	Earth work excavations in foundation In all type of soil including labours, T & P, etc. charges.	1	Cum	12.00		
2.	Sand filling in foundation and In flooring including labours, T & P, Etc. charges.	1	Cum	32.4		
3.	P.C.C work (1:4:8) in foundation And flooring including labours, T&P, Etc., charges.	1	Cum	6.00		
4.	R.R masonry with CM(1:6) in Foundation wall including labours, T&P, etc., charges.	1	Cum	17.00		
5.	R.C.C (1:2:4) with water proofing Work in plinth beam including labours, T&P, etc., charges.	1	Cum	2.00		
6.	1 st class brick work with CM(1:6) in Wall including labours, T&P, etc., charges.	1	Cum	34.00		

SL No.	Description	No	Unity	Qty.	Rate (Rs.)	Amount (Rs.)
7.	G.I sheet for roofing including labours, Fixing, T&P, etc., charges.	1	Sqm	95.00		
8.	MS angle with size (60*50*.6)mm for Truss including all labours, fixing, T&P, Etc., charges.	1	Kg	2196		
9.	R.C.C work (1:2:4) for lintel, self slab Including labours, T&P, etc., charges.	1	Cum	2.5		
10.	Reinforcement work including, cutting, Binding, labours, T&P, etc., charges.	1	Kg	540		
11.	Shuttering & Centering for lintel & self slab Including all materials, labours, T&P, etc., Charges.	1	Sqm	9.00		
12.	MS iron doors & windows shutters Including all materials, fixing, labours, T&P, etc., charges.	12	Sqm	16.00		
13.	MS windows grill including all materials, Fixing, labours, T&P, etc., charges.	8	Kg	120		
14.	12 mm thick Outside plastering with CM(1:6) Including all labours, T&P, etc., charges.	1	Sqm	161		
15.	15 mm thick inside plastering with CM(1:6) Including all labours, T&P, etc., charges.	1	Sqm	150		

SL No.	Description	No	Unity	Qty.	Rate (Rs.)	Amount (Rs.)
16.	P.C.C (1:2:4) work of 25mm thick in Flooring including all materials, labours, T&P, etc., charges.	1	Cum	2.3		
17.	Fixing of Cota tiles in flooring including All materials, labours, T&P, etc., charges.	1	Sqm	88.00		
18.	Panting of inside and outside walls with Cement paint two coats including all Material, labours, T&P, etc., charges.	1	Sqm	315		
19.	Painting of doors & windows with two Coates including all materials, labours, T&P, Etc., charges.	12	Sqm	40		
20.	Painting of MS angles with two coats Including all material, labours, T&P, etc., Charges.	1	RMt.	366		
21.	Wash basins of 3 nos. and sanitary fittings Including all fixing, T&P, etc., charges.	1	L.S	-	-	
22.	Electrical wiring including all materials, Labours, T&P, etc., charges.	1	L.S	-	-	

Total =

SL No. **Description** **No** **Unity** **Qty.** **Rate (Rs.)** **Amount (Rs.)**

Contigecies@3%

Grand Total =